

Ref.	Address		TPO Group	Species	Structure	Num. Stems	Measurements	Locations & Targets	Survey Notes	Recommendation
H1	4 Gibson Rd	Rear Garden	W25	Leyland cypress x5 (<i>X Cuprocyparis leylandii</i>)	Hedge	5	Height (m): 6 Crown Radius (m): 1 DBH (cm): 10cm - 20cm Trees: 5 Life Stage: Early Mature	Located along the right hand side boundary fence line in the rear garden. End nearest the building is becoming Ivy clad. Face has been maintained, but height has been allowed to grow.	Rear garden right hand side	Reduce height to approximately 3m from ground level
T017	4 Gibson Rd	Rear Garden	W25	Cherry (<i>Prunus sp. 'Cherry'</i>)	Tree	1	Height (m): 12 Crown Radius (m): 5 DBH (cm): 45 Life Stage: Mature	Located in the rear garden to the rear boundary to the right hand side. Unable to fully view due to no access - viewed from rear garden of 6. Ganoderma bracket on main stem at approximately 1m from ground level. Crown breaks at approximately 3m from ground level with tight union. Low branches over garden area and neighbouring garden. Failed hungup branches over garden area and neighbouring garden in the mid to lower Crown. Owned by the estate. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: Ganoderma	Fell to ground level and apply eco pellets
G1	5 Gibson Rd	Rear Garden	W25	Mixed species (Mixed species)	Group	1	Height (m): 5m - 10m Crown Radius (m): 4 DBH (cm): 10cm - 20cm Life Stage: Mature	7x young to mature trees located in the rear garden to the left hand side and rear boundary area. 2x mature dominant trees are in contact with the boundary fence of 3. Both trees have historically been pollarded at a height of approximately 3m from ground level. 1x Younger Ash tree is growing through the boundary fence of 3. 1x Maple nearest rear elevation of the building is encroaching on to the building/roof area and some stems are in decline/dead Owned by the estate. Tree in fence line. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: 0	Fell to fence line 1x Young Ash growing through the fence line in to garden of No3. 1x Maple nearest rear elevation of the building - Reduce back from building to allow approximately 2m clearance. Remove deadwood.
T134	8 Gibson Rd	Rear Garden	W25	Prunus (<i>Prunus sp.</i>)	Tree	2	Height (m): 8 Crown Radius (m): 3 DBH (cm): 20cm - 30cm Stems: 2 Life Stage: Mature	Owned by the estate. Target # - building Target # - dwelling. Target # - footpath. - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target.	Located in the rear garden to the left hand side adjacent to the boundary fence line. Multi stemmed at ground level. Large Ganoderma bracket at the base. Main stem to mid crown is ivy clad. Crown spans the area and extends over neighbouring garden.	Fell to ground level and stump grind
T016/0014	9 Gibson Rd	Rear Garden	W25	Oak (<i>Quercus sp.</i>)	Tree	1	Height (m): 10m - 15m Crown Radius (m): 6 DBH (cm): 40cm - 50cm Life Stage: Mature	Located in the rear garden to the right hand side of the rear boundary. Crown breaks at approximately 4m from ground level. Crown suppressed due to adjacent dominant trees. Delamination in various limbs throughout the crown. Deadwood throughout the crown. Owned by the estate. Target # - building Target # - dwelling. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden rear boundary right hand side Pests and Diseases: 0	Remove deadwood

T015/0013	9 Gibson Rd	Rear Garden	W25	Oak (<i>Quercus sp.</i>)	Tree	1	Height (m): 12 Crown Radius (m): 6 DBH (cm): 40cm - 50cm Life Stage: Mature	Located in the rear garden to the left hand side towards the rear boundary area. Ivy on main stem up to approximately 3m from ground level. Crown breaks at approximately 4m from ground level. Previously failed co-dominant branch from low limb over garden of 7. Deadwood in various locations throughout the crown. Crown becoming Low over gardens Owned by the estate. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: 0	Remove deadwood. Crown lift to 3m.
T028	25 Gibson Rd	Rear Garden	W22	Ash (<i>Fraxinus sp.</i>)	Tree	3	Height (m): 10m - 15m Crown Radius (m): 6 DBH (cm): 30cm - 40cm Stems: 3 Life Stage: Mature	Located in the rear garden to the left hand side. Multi stemmed at ground level. Ivy on main stem over garden of No23 to a height of approximately 4m from ground level. Branches encroaching on to the roof area of No23. Owned by the estate. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: 0	Sever ivy. Reduce back from building of No23 to allow approximately 2m clearance
G10	27 Gibson Rd	Rear Garden	W22	Mixed species (Mixed species)	Group	1	Height (m): 10m - 15m Crown Radius (m): 5 DBH (cm): 35	5x young to mature trees Located in the rear garden to the right hand side and in the section of land to the side of the rear garden. Heavily Ivy Clad. Unable to fully view due to extent of ivy. Bat Box attached to central tree at a height of approximately 4m from ground level. Owned by the estate. Target # - building Target # - dwelling. Target # - footpath. Target # - road. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: 0	Sever ivy to 3x trees in the rear garden to the right hand side
T32	29 Gibson Rd	Side Of	W22	Elder (<i>Sambucus nigra</i>)	Tree	1	Height (m): 0m - 5m Crown Radius (m): 2 DBH (cm): 25 Life Stage: Over Mature	Located in the area to the left hand side of the rear garden to the rear boundary fence line adjacent to the neighbouring driveway. Located in raised soil with a progressive lean towards the footpath. Heavily in decline. Owned by the estate. Target # - footpath. Target # - road. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Side of the rear garden Pests and Diseases: 0	Fell to ground level

T44	35 Gibson Rd	Rear Garden	W24	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	2	Height (m): 5m - 10m Crown Radius (m): 3 DBH (cm): 10cm - 20cm Stems: 2 Life Stage: Semi Mature	Located in the rear garden adjacent to the rear boundary fence. Twin stemmed at ground level. Dominant stem forks in to 2x stems at approximately 0.5m from ground level with tight union. Rear single stem is in conflict with the boundary fence post. Ivy clad from ground level in to the upper crown. Deadwood throughout the crown showing signs of Ash Dieback. Residents rear of the rear boundary has cut off branches which overhung their garden and chuck them back in to the garden of 35 Gibson Rd. Owned by the estate. Tree in fence line. Target # - building Target # - dwelling. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: Ash Dieback Infection Level 2: 25% to 50%	Fell to ground level and apply eco pellets
T160	40 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 7 Crown Radius (m): 2 DBH (cm): 0cm - 10cm Life Stage: Semi Mature	Located in the rear garden to the left hand side. Growing through boundary chain link fence line. Previously been creeper clad with signs of the tree Growing around the dominant creeper stems. Undesirable species for the location. Owned by the estate. Tree in fence line. Target # - dwelling. Target # - footpath. - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target.	Rear garden	Fell to fence height and apply eco pellets
T144	41 Gibson Rd	Rear Garden	W24	Willow (<i>Salix</i> <i>sp.</i>)	Tree	2	Height (m): 7 Crown Radius (m): 3 DBH (cm): 0cm - 10cm Stems: 2 Life Stage: Dead	Located in the rear garden to the right hand side towards the rear boundary. Twin stemmed at ground level. Leaning towards the rear boundary fence line. Suppressed by adjacent dominant tree. Owned by the estate. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target.	Rear garden	Fell to ground level
G15	55/57 Gibson Rd	Rear Garden	W23	Mixed species (<i>Mixed species</i>)	Group	1	Height (m): 10m - 15m Crown Radius (m): 5 DBH (cm): 45 Life Stage: Mature	8-9 x trees located along the fence line of 55 & 57 Gibson Rd. Most trees are ivy clad. Unable to fully view due to the extent of the ivy. Deadwood throughout the crown. Owned by the estate. Target # - building Target # - dwelling. - Within drip line. - Within 1x tree height. - Occupancy - Occasionally(2). - Not practical to move the target.	Rear garden Pests and Diseases: 0	Sever ivy to all trees

T148	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	3	Height (m): 13 Crown Radius (m): 4 DBH (cm): 10cm - 20cm Stems: 3 Life Stage: Early Mature	<p>Located in the rear garden to the right hand side, near the rear elevation of the building.</p> <p>Roots lifting rear patio area.</p> <p>Multi stemmed at ground level.</p> <p>Branches in contact with the rear elevation and roof of building.</p> <p>Internal epicormic growth showing signs of Ash Dieback.</p> <p>Owned by the estate.</p> <p>Target # - building</p> <p>Target # - dwelling.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Fell to ground level and apply eco pellets
T151	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 9 Crown Radius (m): 2 DBH (cm): 0cm - 10cm Life Stage: Semi Mature	<p>Young Ash located in the rear garden to the rear boundary.</p> <p>Single stemmed growing in to the crown of adjacent Ash.</p> <p>No long term future in current condition and location.</p> <p>Owned by the estate.</p> <p>Target # - dwelling.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Fell to ground level and apply eco pellets
T152	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 11 Crown Radius (m): 2 DBH (cm): 10cm - 20cm Life Stage: Semi Mature	<p>Located in the rear garden to the rear boundary.</p> <p>Heavily suppressed and leaning in to garden area.</p> <p>No long term future in current condition and location.</p> <p>Owned by the estate.</p> <p>Target # - dwelling.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Fell to ground level and apply eco pellets
T153	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 10m - 15m Crown Radius (m): 6 DBH (cm): 30cm - 40cm Life Stage: Mature	<p>Located in the rear garden to the rear boundary.</p> <p>Buttressing at base.</p> <p>Base in contact with the rear boundary fence line.</p> <p>Crown breaks at approximately 5m from ground level.</p> <p>Crown spans the rear boundary area and extends over neighbouring gardens.</p> <p>Deadwood throughout the crown with signs of Ash Dieback.</p> <p>Tree in fence line.</p> <p>Target # - building</p> <p>Target # - dwelling.</p> <p>Target # - footpath.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Pests and Diseases: Ash Dieback Infection Level 1: 0% to 25%
T154	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	2	Height (m): 11 Crown Radius (m): 3 DBH (cm): 20cm - 30cm Stems: 2 Life Stage: Early Mature	<p>2x Ash in close proximity to each other, located in the rear garden to the right hand side near the rear boundary.</p> <p>Base if stems in contact with boundary chain link fence.</p> <p>Slight Lean over garden of No59 due to being suppressed by adjacent dominant tree.</p> <p>No long term future in current condition and location.</p> <p>Owned by the estate.</p> <p>Tree in fence line.</p> <p>Target # - dwelling.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Fell to ground level and apply eco pellets.

T155	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 11 Crown Radius (m): 2 DBH (cm): 10cm - 20cm Life Stage: Semi Mature	<p>1x Ash in close proximity to each other located in the rear garden to the right hand side.</p> <p>Base and stem in contact with adjacent chain link fence.</p> <p>Suppressed by adjacent dominant trees.</p> <p>No long term future for its location.</p> <p>Owned by the estate.</p> <p>Tree in fence line.</p> <p>Target # - dwelling.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden	Fell to ground level and apply eco pellets
T157	57 Gibson Rd	Rear Garden	W23	Ash (<i>Fraxinus</i> <i>sp.</i>)	Tree	1	Height (m): 11 Crown Radius (m): 2 DBH (cm): 0cm - 10cm Life Stage: Semi Mature	<p>Located in the rear garden to the right hand side in contact with the boundary chain link fence.</p> <p>Forks in to 2x stems at approximately 1.5m from ground level.</p> <p>Crown extends over garden of No59.</p> <p>No long term future in current location.</p> <p>Early signs of Ash Dieback.</p> <p>Owned by the estate.</p> <p>Tree in fence line.</p> <p>Target # - dwelling.</p> <p>Target # - footpath.</p> <ul style="list-style-type: none"> - Within drip line. - Within 1x tree height. - Occupancy - Frequent(3). - Not practical to move the target. 	Rear garden Pests and Diseases: Ash Dieback	Fell to ground level and apply eco pellets