



HALLWOOD
ASSOCIATES
ARBORICULTURAL AND WOODLAND CONSULTANTS

**TITLE: Arboricultural Impact
Assessment:**
560 Sipson Road, West Drayton,
UB7 0JD

DATE: 20th June 2022

PREPARED BY: Dominic Poston

REF: HWA10759-APIII



ARBORICULTURAL IMPACT ASSESSMENT (APIII)

560 Sipson Road, West Drayton, UB7
0JD

HWA10759-APIII

20 June 2022

Prepared for:

P&S Hoteliers Ltd

Prepared by:

Dominic Poston

DipArb (RFS) FArborA MICFor CEnv BSc HDip

Hallwood Associates Ltd.

Telephone: 01621 770168

Email: enquiries@hallwoodassociates.com

Web: www.hallwoodassociates.com

Report Version Control:

Version	Date	Author	Change description
1.0	20/06/2022	Dominic Poston	First Issue

SUMMARY

--	--	--	--

The purpose of this report is to deliver specific information pertaining the arboricultural implications created by the proposed development. In accordance with the feasibility and planning sections of BS5837:2012 "Trees in relation to design, demolition and construction – Recommendations", trees deemed to be within the influencing distance of the projected construction have been evaluated for quality, longevity, and initial maintenance requirements.

This report provides sufficient information for the Local Planning Authority (LPA) to consider the effect of the proposed development on local character from a tree perspective. It is fully compliant with the BS 5837 advice relating to the planning application stage of the process and it meets national standard planning application validation requirements.

In this circumstance it is intended to construct a new hotel at 560 Sipson Road, West Drayton, UB7 0JD.

The arboricultural related implications of the proposal are as follows:

- **Implications on Construction:** Tree protection will be required in order to protect off site trees.
- **Cultural Implications for Retained Trees:** One low value group will require lateral reduction in order facilitate development.
- **Implications on Local Character:** None reasonably foreseeable.
- **Post Development Implications:** None reasonably foreseeable.
- **Post Planning Permission:** Subject to achieving Planning Permission, a detailed Arboricultural Method Statement and Tree Protection Plan will be required. This will include the following: fencing type, ground protection measures, access facilitation pruning specification, phasing and an extensive auditable monitoring schedule.



Dominic Poston

DipArb (RFS) FARborA MICFor CEnv BSc HDip
 Director
 Hallwood Associates Ltd
 20/06/2022

Table of Contents

Part One: Introduction.....	5
1. Particulars of Instruction	6
2. Authorship.....	6
3. Report References.....	6
4. Scope of Report.....	6
5. Limitations.....	7
6. Methodology	8
7. The Site	9
 Part Two: Arboricultural Impact Assessment.....	 10
8. The Proposal	11
9. Arboricultural Features	11
10. Impact Assessment	11
11. Mitigation	12
 Part Three:(HoT) Arboricultural Method Statement.....	 13
 Appendix A: Tree Survey Schedule	 14
 Appendix B: Plans	 17

Part One: Introduction

This report is formulated in accordance with the recommendations contained within BS 5837, providing appropriate and sufficient information to enable the relevant Local Planning Authority (LPA) to consider the effects of the proposed development upon existing trees and local character. It includes an **Arboricultural Impact Assessment**, a **Tree Protection Plan** and a heads of terms **Arboricultural Method Statement** detailing how retained trees may be successfully integrated into the design. It is fully in line with the BS 5837 advice relating to the planning application stage of the process highlighted in Table B1 reproduced below:

Table B.1 Delivery of tree-related information into the planning system

Stage of process	Minimum detail	Additional information
Pre-application	Tree survey	Tree retention/removal plan (draft)
Planning Application	<ul style="list-style-type: none"> Tree survey (in the absence of pre-application discussions) Tree retention/removal plan (finalized) Retained trees and RPAs shown on proposed layout Strategic hard and soft landscape design, including species and location of new tree planting Arboricultural impact assessment 	<ul style="list-style-type: none"> Existing and proposed finished levels Tree production plan Arboricultural method statement – heads of terms Details for all special engineering within the RPA and other relevant construction details
Reserved Matters / Planning Conditions	<ul style="list-style-type: none"> Alignment of utility apparatus (including drainage), where outside the RPA or where installed using a trenchless method Dimensioned tree protection plan Arboricultural method statement-detailed Schedule of works to retained trees, e.g., access facilitation pruning Detailed hard and soft landscape design 	<ul style="list-style-type: none"> Arboricultural site monitoring schedule Tree and landscape management plan Post-construction remedial works Landscape maintenance schedule

Table 1: Delivery of tree-related information into the planning system

1. Particulars of Instruction

- 1.1 Hallwood Associates Ltd (HWA) are instructed by P&S Hoteliers Ltd to provide specialist arboricultural advice in accordance with the principles laid out within British Standard BS 5837: 2012 "Trees in relation to design, demolition and construction – Recommendations (BS) with regards to a planning application being made at 560 Sipson Road, West Drayton, UB7 0JD

2. Authorship

- 2.1 Dominic Poston is a chartered arboriculturist and chartered environmentalist. He holds the Royal Forestry Society's Professional Diploma in Arboriculture, is a fellow member of the Arboricultural Association and a registered consultant with the Institute of Chartered Foresters. The findings in this report are reached through site observations and conclusions are made in light of his experience. Details are available upon request or at www.hallwoodassociates.com.

3. Report References

- 3.1 This Arboricultural Impact Appraisal is informed by reference material, including the following:
- BS 5837: (2012) Trees in relation to Design, Demolition and Construction – Recommendations;
 - BS 3998: (2010) Tree Works – Recommendations;
 - National Joint Utilities Group (2007) Volume 4, Issue 2: Guidelines for the planning, installation and maintenance of utility apparatus in proximity to trees;
 - DTLR (2001) Principles of Tree Hazard Assessment and Management – David Lonsdale
- 3.2 The following drawings and/or reports aided production of this Impact Assessment:
- Existing site layout
 - Proposed site layout

4. Scope of Report

- 4.1 This report and all plans appended to it have been formulated using guidance given in the British Standard 5837: 2012 'Trees in relation to design, demolition and construction – Recommendations'.
- 4.2 The tree survey was carried out independently, as far as possible, of the proposed new layout, as recommended in the British Standard.
- 4.3 The survey contains details of the size, condition and retention category of each tree which may be affected by the proposed development.
- 4.4 The retention category is derived from the British Standard which allows arboriculturists to place trees in certain bands so that impacts can be appropriately quantified and managed; broadly defined as follows:
- A Category - High quality and value - such a condition as to be able to make a substantial contribution (a minimum of 40 years is suggested);

PART ONE: INTRODUCTION

- B Category - Moderate quality and value - those in such a condition as to make a significant contribution (a minimum of 20 years is suggested);
- C Category - low quality and value – currently in adequate condition to remain until new planting could be established (a minimum of 10 years is suggested).
- U Category - in such a condition that any existing value would be lost within 10 years and which should, in the current context be removed for reasons of sound Arboricultural management.


5. Limitations

- 5.1 The potential effect of development on trees, whether statutorily protected (e.g. by tree preservation order or by their inclusion within a conservation area) or not, is a material consideration that is taken into account in dealing with planning applications. HWA have not checked whether trees on site are statutorily protected as this can delay production of the report. The applicant must carry out a statutory tree protection check if you intend to undertake any works prior to formal planning consent being issued.
- 5.2 All rights in this report are reserved. Its content and format are for the exclusive use of the addressee in dealing with this site. It may not be sold, lent, hired out or divulged to any third party not directly involved in this site without the written consent of Hallwood Associates Limited.
- 5.3 This report is restricted to those trees shown on the attached plans and described in the tree survey schedule. All plans and discussions within this report are based entirely on the drawings provided to Hallwood Associates and referenced above. Any material planning changes after the date of report issue will invalidate this report.
- 5.4 Hallwood Associates Ltd have undertaken their tree survey with due care and attention to identify accurately all tree species present at the time of survey. However, where surveys are undertaken when trees are out of leaf, if access is not granted or clear, or where insufficiently accurate tree location detail is provided by the client; trees may be grouped and general tree species composition listed.
- 5.5 The statements, findings and recommendations made within this report do not take into account any effects of extreme climate and weather incidences, vandalism, changes in the natural and built environment around the tree(s) after the date of this report, nor any damage whether physical, chemical or otherwise. Hallwood Associates cannot accept any liability in connection with the above factors, nor where recommended tree management is not carried out in accordance with modern tree health care techniques, within any proposed timeline.
- 5.6 Due to the above statements, this report remains valid for two years from the date of issue only.

6. Methodology

- 6.1 Each tree was surveyed and given a number corresponding to the provided plan(s) found at Appendix B. For each group or individual information was collected as recommended at 4.4.2.5 of BS 5837. The survey was preliminary in nature and did not involve aerial or detailed inspection. This data is held within the tree schedule which can be found at Appendix A.
- 6.2 BS5837 recommends that trees within categories A-C (where A is highest quality) are a material consideration in the development process. However, it should be noted that young trees with a stem diameter less than 150mm may be considered for relocation. Category U trees are those that will not be expected to exist for long enough to justify their consideration in the planning process. The A-C categories are combined with the numbers 1, 2 or 3. These numbers signify whether the justification for the category was based on arboricultural, landscape or cultural/conservation values respectively. The tree categories are illustrated on the plans with colour coding. Category A trees are light green, category B are mid blue, category C are grey and category U are dark red.
- 6.3 Where category U trees are notable for their conservation, heritage or landscape value, even though only for the short term, they may be upgraded, although they might be suitable for retention only where issues concerning their safety can be appropriately managed.
- 6.4 Section 4.6 of BS5837 recommends that the trunk diameter measurement for each tree is used to calculate the root protection area (RPA), which can then be interpreted to identify the design constraints and, once a layout has been developed to be protected by barriers (tree protection plan (TPP)).
- 6.5 Following inspection and grading of the trees, the information listed in Appendix A is used to provide constraints guidance to the project architect based on the locations of the best trees. All U trees are ignored as they not of good enough quality to be considered as a material constraint on development.
- 6.6 The enclosed tree protection plan (TPP) shows the trees proposed for retention, their relevant RPA and provisional positions for protective fencing and ground protection.

7. The Site



This aerial image is provided courtesy of Google. The yellow line indicates the approximate site boundary and is illustrative only.

- 7.1 The site was visited by Dominic Poston on 15 June 2022 and comprises brownfield land on the site of a former club building.
- 7.2 The existing arboricultural features are restricted to offsite boundary vegetation. These groups and individuals contribute to the overall character of the site.
- 7.3 The British Geological Survey Online Geology Map indicates the soils on site are London Clay

Part Two:

Arboricultural Impact Assessment

This arboricultural impact assessment has taken account of all the recommendations set out in BS 5837 section 5.4, as reproduced below:

5.4 Arboricultural impact assessment

5.4.1 The project arboriculturist should use the information detailed in **5.2** and **5.3** to prepare an arboricultural impact assessment that evaluates the direct and indirect effects of the proposed design and where necessary recommends mitigation.

5.4.2 The assessment should take account of the effects of any tree loss required to implement the design, and any potentially damaging activities proposed in the vicinity of retained trees. Such activities might include the removal of existing structures and hard surfacing, the installation of new hard surfacing, the installation of services, and the location and dimensions of all proposed excavations or changes in ground level, including any that might arise from the implementation of the recommended mitigation measures. In addition to the impact of the permanent works, account should be taken of the buildability of the scheme in terms of access, adequate working space and provision for the storage of materials, including topsoil.

NOTE Scaled cross-sections and other drawings might be required to demonstrate the feasibility of the proposals (see Annex B).

5.4.3 As well as an evaluation of the extent of the impact on existing trees, the arboricultural impact assessment should include:

- a) the tree survey (see **4.4**);
- b) trees selected for retention, clearly identified (e.g., by number) and marked on a plan with a continuous outline;
- c) trees to be removed, also clearly identified (e.g., by number) and marked on a plan with a dashed outline or similar;
- d) trees to be pruned, including any access facilitation pruning, also clearly identified and labelled or listed as appropriate;
- e) areas designated for structural landscaping that need to be protected from construction operations in order to prevent the soil structure being damaged;
- f) evaluation of impact of proposed tree losses;
- g) evaluation of tree constraints (see **5.2**) and draft tree protection plan (see **5.5**);
- h) issues to be addressed by an arboricultural method statement (see **6.1**), where necessary in conjunction with input from other specialists.

PART TWO: ARBORICULTURAL IMPACT ASSESSMENT

8. The Proposal

8.1 The proposal is to construct a new hotel.

9. Arboricultural Features

9.1 There are eleven (11) trees and One (1) group of trees which have been categorised within the site. Below is a visual representation of the tree quality categorisation across the surveyed trees.




Figure 1: Tree categorisation (BS 5837: 2012)

9.2 A schedule of tree condition and category of retention (see 4.4 above) is attached at Appendix A.

10. Impact Assessment

10.1 Two (2) Category 'U' trees have been identified for removal due to management reasons. Their removal would have been required irrespective of any development proposal and it is therefore considered inappropriate to imply any loss accruing.

10.2 Following a review of the proposed layout, an assessment of the impact on trees, both during and after development, and those that need protection using special precautions, is summarised below in Table 2:

PART TWO: ARBORICULTURAL IMPACT ASSESSMENT

British Standard 5837 Category & Reference Number			Impact	Reason	Mitigation
A	B	C			
None	None	None	Trees to be removed	Building construction and/or proximity	N/A
None	None	H1	Trees to be pruned	To make space for development	All works to BS 3998.
None	None	None	RPA disturbance	Removal or installation of surfaces/ structures/ landscaping	N/A
None	None	None	Post development considerations	Shading/encroachment/ dominance	N/A

Table 2: Arboricultural Implications (T = Tree, G = Group, H = Hedge)

NB: All retained trees will be protected during development by using fencing and/or ground protection, and only those requiring special precautions to limit the impact of encroachment are listed in Table 1.

10.3 The impact of tree pruning.

The proposed tree pruning involves the removal of second and third order laterals or subordinate branches only and all works can be undertaken in full accord with the principles laid out in BS 3998.

11. Mitigation

11.1 Tree Planting.

Given the lack of direct arboricultural impact, it is not considered necessary or appropriate to specify new tree planting in mitigation.

Part Three:

(Heads of terms summary)

Arboricultural Method Statement

An Arboricultural Method Statement details how retained trees are to be protected and how operations that may affect trees will be carried out to minimise any adverse impact on them. The details of how the site will be managed can only be finalised once the post-consent detailed planning begins. As explained in clause 5.5.6 of BS 5837, it is normally sufficient to list a heads of terms summary of the issues requiring more detailed consideration once consent is issued. The following list identifies those issue requiring consideration on this site:

- Details of retained arboricultural consultant and scheme of arboricultural supervision.
- Details of a 'toolbox' talk on arboricultural matters to be included in induction training for all operatives on site.
- The order of work on site, including demolition, site clearance and building work.
- Erection and maintenance of tree protection measures.
- Roles and responsibilities (including contact details) with regard tree management and protection on site.
- How accidents and emergencies involving trees will be managed.
- Details of facilitation pruning and access into site.
- The parking arrangements and final site compound (including welfare facilities) for workers and visitors.
- Areas for loading and unloading of materials and storage of materials and plant.
- How machinery and equipment (such as excavators, cranes and their loads, concrete pumps and piling rigs) will enter, move on, work on, and leave the site.
- Details of earthworks, grading and mounding and removal of spoil, including any planned lowering or raising of ground levels.
- Final service and utility locations, including the method of installation when near trees.
- How post-construction impacts through compaction to soil near trees will be ameliorated.

Appendix A: Tree Survey Schedule

(Ref) No.	Species	Height (m)	Stem diameter (mm)	Branch spread N (m)	Branch spread E (m)	Branch spread S (m)	Branch spread W (m)	Crown Clearance (m)	Structural Condition	Physiological Condition	Life Stage	Observations	Preliminary Recommendations (irrespective of development proposals)	Remaining contribution (yrs)	Value categorisation (BS 5837)
1	Leland cypress	15	375	4.5	2.5	2	4	3	Fair	Fair	M	off site tree	None	40+	C
2	Leyland cypress	15	400	4	5.5	2	1	3	Fair	Fair	M	off site tree	None	40+	C
3	Norway maple 'Goldsworth Purple'	6	175	1.5	2	3.5	1.5	2	Fair	Fair	EM	off site tree	None	40+	C
4	Leyland cypress	10	300; 125	2	1	2	1.5	2	Poor	Poor	EM	off site tree	None	<10	U
5	Norway maple 'Goldsworth Purple'	10	325	2	3.5	2	4	1.8	Fair	Fair	EM	off site tree	None	40+	C
6	Alder	12	175	1.5	1.5	1.5	1.5	7	Fair	Fair	EM	off site tree	None	40+	C

(Ref) No.	Species	Height (m)	Stem diameter (mm)	Branch spread N (m)	Branch spread E (m)	Branch spread S (m)	Branch spread W (m)	Crown Clearance (m)	Structural Condition	Physiological Condition	Life Stage	Observations	Preliminary Recommendations (irrespective of development proposals)	Remaining contribution (yrs)	Value categorisation (BS 5837)
7	Alder	12	150	1.5	1.5	1.5	1.5	5	Fair	Fair	EM	off site tree	None	40+	C
8	Sycamore	6	150	2	2	2	2	2	Poor	Poor	EM	In accessible. Located between south boundary fence and south elevation of the derelict property	Fell	20+	U
9	Acacia	14	600	4	4	4	4	4	Good	Good	M	off site tree located 12.5m from fence/boundary wall	None	40+	B
10	Acacia	15	350	3.5	3.5	3.5	3.5	4	Good	Good	M	off site tree located 9m from fence/boundary wall	None	40+	B
11	Acacia	14	275	3	3	3	3	4	Good	Good	M	off site tree located 10, from fence/boundary wall	None	40+	B
H1	Portugese Laurel	7	125	1	2	1	2	2	Fair	Fair	EM	off site laurel hedge/screen. 50+ stems. Ave stem diameter 90mm	Face back to make space on application site.	40+	C

Appendix B: Plans



APPENDIX B

Figure 1: Tree Constraints Plan HWA10579-TCP



SIPSON ROAD

NOTE:
This drawing is to be read in conjunction with all other relevant technical information, statutory approvals, specifications and 3rd party information. Do not scale from this drawing. Use only dimensions provided. All dimensions and levels to be checked on site and all discrepancies must be reported to the drawings author immediately. This drawing was based upon drawings provided by the client. The original of this drawing was produced in colour and monochrome versions cannot be relied upon. This drawing is to be used only for the purposes indicated. It is the responsibility of the contractor to ensure any necessary consents are in place. This drawing is copyright and the property of Hallwood Associates Ltd (HWA) and must not be reproduced without prior written agreement.



- Tree stem location and value category according to BS 5837:
 - Red - No value
 - Grey - Low value
 - Blue - Moderate value
 - Green - High value
- Trees/Hedges proposed for removal to facilitate development.
- Proposed line of tree protection fencing.

Rev.	Description.	Date.
 <div>HALLWOOD ASSOCIATES LTD t: 01621 770168 e: enquiries@hallwoodassociates.com</div>		
Client: Phull Empire Ltd		
Site: 560 Sipson Rioad, West Drayton, UB7 0JF		
Drawing Title: Tree Constraints Plan 1 of 1		
Date:	17.06.22	Drawn By: DAP
Scale:	1:200 @ A3	Checked By: GLP
Drawing Number: HWA10759-TCP		Rev.

APPENDIX B

Figure 2: Tree Protection Plan HWA10759-TPP



H1

HWA10759-TPP



SIPSON ROAD


NOTE:

This drawing is to be read in conjunction with all other relevant technical information, statutory approvals, specifications and 3rd party information. Do not scale from this drawing. Use only dimensions provided. All dimensions and levels to be checked on site and all discrepancies must be reported to the drawings author immediately. This drawing was based upon drawings provided by the client. The original of this drawing was produced in colour and monochrome versions cannot be relied upon. This drawing is to be used only for the purposes indicated. It is the responsibility of the contractor to ensure any necessary consents are in place. This drawing is copyright and the property of Hallwood Associates Ltd (HWA) and must not be reproduced without prior written agreement.

SCALE BAR 1:200



SCALE BAR 1:500



- Tree stem location and value category according to BS 5837:
 - Red - No value
 - Grey - Low value
 - Blue - Moderate value
 - Green - High value
- Trees/Hedges proposed for removal to facilitate development.
- Proposed line of tree protection fencing.

Rev.	Description.	Date.
 <div>HALLWOOD ASSOCIATES LTD t: 01621 770168 e: enquiries@hallwoodassociates.com</div> <div>HALLWOOD ASSOCIATES ARBORENTURAL AND WOODLAND CONSULTANTS</div>		
Client: Phull Empire Ltd		
Site: 560 Sipson Road, West Drayton, UB7 0JF		
Drawing Title: Tree Protection Plan (Basement) 1 of 2		
Date:	17.06.22	Drawn By: DAP
Scale:	1:200 @ A3	Checked By: GLP
Drawing Number: HWA10759-TPP		Rev.