



**HADDONSTONE** TECHNICAL SPECIFICATION SHEET **M90**

Haddonstone Ltd +44 (0)1604 770711 info@haddonstone.co.uk • Haddonstone (USA) Ltd 866 733 8225 stone@haddonstone.com

**HADDONSTONE CILLS**

Installation of Cills to be generally in accordance with British Standards and the latest regulations, particularly regarding ventilation requirements. Cills should be bedded with mortar (1:1.5 cement/lime/sand) only below the ends of the stoolings, to prevent fracture of the Cills in the event of thermal movement and differential settlement. Multiple section Cills should be bedded under stoolings and at ends of sections only. The open joint should be pointed with mortar (1:1.6 cement/lime/sand) on completion of the masonry. Cills should be provided with a damp proof course for the full length and width of the Cill, this should be laid on a bed and turned up behind the Cill. Horizontal and vertical damp proof courses should be fitted at ends of the Cill, damp proof course width should allow for a 25mm (1") projection into cavity and depth of rebate.

Fired clay and reconstructed masonry units should not be bonded, but should be effectively separated by either a vertical or horizontal movement joint or slip plane, since their movements are different in magnitude and in kind. The risk of cracking is increased where stronger mortars than those recommended are used.

Adequate provision for movement must be made at the design stage.

© 2020 Haddonstone Ltd All rights reserved      Do not scale      www.haddonstone.com

**KEYMER**  
EST. 1588

**SHIRE - OCKLEY MIX**

Ockley Mix is a blend mixed from 50% Heritage and 50% Priory Shire tiles.

Nominal size	265 x 165mm
Gauge	100mm
Coverage	60 / sq.m
Weight per 1,000	1,300kg
Weight per pallet	715kg
Quantity per pallet	550

**Download Brochure**

**Request Sample**

**TECHNICAL DRAWING**

Featuring pre-tensioned spring balances in place of traditional weights and pulleys, these double glazed windows offer classic period styling combined with the latest timber window technology and skilled craftsmanship.



**IMPERIAL**  
handmade bricks

Grindle House Farm, Grindle Road, Grindle, Near Shifnal, Shropshire, TF11 9JR  
01952 750 816 • sales@imperialbricks.co.uk  
www.imperialbricks.co.uk

**G N P**

Chartered Architects

4 Goodman Gardens,  
Woughton on the Green,  
Milton Keynes. MK6 3EP

Tel : 01908 200002

Project Title:  
**'Tavistock'**  
27 Dane Road,  
Northwood,  
HA6 2BX

Drawing Title:  
**As Proposed - illustrations  
of proposed materials**  
Client  
**Mrs P. Sander**

Scale  
-  
Drawn  
June '2022

Drawing No. **A3 original** Rev  
635.22.64  
This drawing is copyright