

48 Murray Road – Condition 16 – Access Road specification – to be read in conjunction with Corsican Associates Detailed Hard Landscape proposals (ref: 21/026-02)

Permeable -

Surface Course

40mm of maximum size.AC 10 Open Graded
asphalt, Max 100/150 Pen to BS EN 13108-1:2006

Base Course

80mm of maximum size AC20 open graded asphalt.

Subbase

300mm thick type 3 granular sub-base to SHW

Clause 805 laid in well compacted layers.on Terram

1000 or equal approved Membrane .

