

## 9 King Edwards Road, Ruislip: External Wall Insulation



Visibility of exposed beam ends to be preserved

Tile creasing course to be removed

The whole surface of all walls above damp proof course to have external wall insulation applied (using 120mm mineral wool insulation) on the KLEIB 'W' system, in accordance with manufacturer's instructions as detailed in the accompanying document:

*KLEIB\_SYSTEM\_application\_instructions\_NSAI 08112024 (for mineral wool insulation).pdf*

Surface to be rendered with KLEIB silicone render to match existing finish colour.

Scaffolding to be erected within neighbour's boundary, with neighbour's permission (already granted, provided sufficient clearance for easy passage of child buggies is maintained, with no obstruction of manholes).

Pea shingle course to be retained between wall and property boundary

Area below damp proof course to be fitted with separate recessed insulation layer to ensure no bridging of dpc.

Any existing render that extends below dpc to be cut back and removed