


SIDE ELEVATION (east)

**GENERAL - New materials used in exterior work to match existing.**

- WALLS - To be facing brickwork
- WINDOWS - All new windows to be double glazed, profile to match existing + set within opening to match existing.
  - **Side windows to be obscure glazing, top opening to be 1.7m from FFL.**
  - **Side window at boundary to be obscure glazing & fixed light.**
- DOORS - All new doors to be double glazed, profile to match existing + set within opening to match existing.
- RWP & GUTTERS - to be UPVc black to match existing.

- ROOFLIGHTS - 'Velux' or similar. Projection to be max. 150mm beyond the plane of the roof-slope & flat roof.
- EAVES - Detail to match existing, ie height of fascia & soffit width + colour of soffit and fascia
- ROOF - **Pitch roof** - Plain red/brown roof tiles to match existing. Tile type, size & colour to match existing. **Flat roof** - to be GRP grey/green colour
- DORMER - Dormer to be lower than top of existing roof ridge.
- JULIET BALCONY - External face including side cheeks to be red/brown roof tiles, colour to match main roof tiles.
- Railing to be min 1.1 meter high from SILL Strength - handrail pressure must be able to take 1.5kN/m and to meet BS 6180:2011 and be tested for impact loading in accordance with BS 6206 and BS EN 12600.



SIDE ELEVATION (west)

This application seeks to follow the same design approach achieved at 106 Harley Drive

REF - 2024/APP/2019/876

and

4 Chamberlain Way

REF - 48300/APP/2017/677

Pre-planning report  
Dated: 29 March 2022  
Ref: 9856/PRC/2021/264

PROPOSED



0 1m 2m 3m 4m 5m 6m 7m 8m 9m  
scale - 1 : 100 @ A3

tel : 0796 222 3141  
email : sandeep@sskarchitects.co.uk

Purpose - Householder planning application

All dimensions to be checked on site. All omissions & discrepancies to be reported to the designer.	PROJECT: 12 Chamberlain Way, Pinner, HA5 2AY	DATE: 26/05/2022
(C) SSK architects owns the copyright of this drawing which must not be reproduced in whole or part without the written permission.	DWG NO: <b>ELEVATION</b>	REVISION: <b>14</b>